

**NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM**

(Type all entries - complete applicable sections)

STATE: Missouri	
COUNTY: Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME

COMMON:	Market Square Historic District
AND/OR HISTORIC:	

2. LOCATION

STREET AND NUMBER: Boundaries as shown on Map #3 *			
CITY OR TOWN: St. Joseph			
STATE Missouri	CODE 64501	COUNTY: Buchanan	CODE 021

3. CLASSIFICATION

CATEGORY (Check One)	OWNERSHIP	STATUS	ACCESSIBLE TO THE PUBLIC
<input checked="" type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Building <input type="checkbox"/> Structure <input type="checkbox"/> Object	<input type="checkbox"/> Public <input type="checkbox"/> Private <input checked="" type="checkbox"/> Both	<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress	Yes: <input checked="" type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input type="checkbox"/> No

PRESENT USE (Check One or More as Appropriate)				
<input type="checkbox"/> Agricultural <input checked="" type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment	<input type="checkbox"/> Government <input checked="" type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum	<input type="checkbox"/> Park <input type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific	<input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) _____	<input type="checkbox"/> Comments _____

4. OWNER OF PROPERTY

OWNER'S NAME: Multiple private ownership	STATE: Missouri
STREET AND NUMBER:	
CITY OR TOWN: St. Joseph	
STATE: Missouri	
CODE: 64501	CODE: 29

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC: Recorder of Deeds, Buchanan County Courthouse	COUNTY: Buchanan
STREET AND NUMBER: 5th and Jules streets	
CITY OR TOWN: St. Joseph	
STATE: Missouri	
CODE: 64501	CODE: 29

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY: Missouri Historic Sites Catalogue	ENTRY NUMBER	DATE
DATE OF SURVEY: <input type="checkbox"/> Federal <input checked="" type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local		
DEPOSITORY FOR SURVEY RECORDS: State Historical Society of Missouri		
STREET AND NUMBER: Corner, Hitt and Lowry streets		
CITY OR TOWN: Columbia	STATE: Missouri	CODE: 65201
		CODE: 29

FOR NPS USE ONLY

*Congressional District #6
The Hon. W. R. Hull, Jr. House of Representatives

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

4. #1 MARKET SQUARE HISTORIC DISTRICT
1. John Edward Kirschner
101 - 103 Market Place
102 - 104 S. Third Street
218, 218 ½, 220 Felix Street
St. Joseph, Missouri 64501
 2. William Waris, et al
105, 107 Market Place
106 S. Third Street
St. Joseph, Missouri 64501
 3. Charles R. Willits & Wife
108, 122 S. Third Street
227, 229 Edmond Street
St. Joseph, Missouri 64501
 4. William Rothstein, Sidney Rothstein, Leonard Rothstein
109, 111, 113, 115 Market Place
110, 112, 114, 116 S. Third Street
St. Joseph, Missouri 64501
 5. Louis Blamar
117, 119, 121, 123 Market Place
118, 120 S. Third Street
St. Joseph, Missouri 64501
 6. Nate Rothstein
223, 225 Edmond Street (vacant lot)
St. Joseph, Missouri 64501
 7. Mrs. Bartlett Boder
402 Felix Street
409, 411 Edmond Street
St. Joseph, Missouri 64501

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

6. #1

MARKET SQUARE HISTORIC DISTRICT

Missouri State Historical Survey

(state)

1971

Missouri State Park Board

P. O. Box 176

1204 Jefferson Building

Jefferson City, Missouri 65101

Code: 29

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input type="checkbox"/> Good	<input checked="" type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

DESCRIPTION OF BOUNDARIES OF AREA NOMINATED TO NATIONAL REGISTER OF HISTORIC PLACES (see map #3):

Market Square Historic District is bounded on the east by the alley in city block 51 running from the northeast corner where Felix Street and the alley intersect to the southeast corner where Edmond Street and the alley intersect and by Third Street running from the northeast corner where Francis and Third streets intersect to the northeast corner where Felix and Third streets intersect; on the west by Market Place running from the northwest corner where Francis Street and Market Place intersect to the southwest corner where Edmond Street and Market Place intersect; on the north by Francis Street running from the northwest corner where Francis Street and Market Place intersect to the northeast corner where Francis and Third streets intersect and by Felix Street running from the northeast corner where Felix and Third streets intersect to the northeast corner where Felix Street and the alley intersect; and on the south by Edmond Street running from the southwest corner where Edmond Street and Market Place intersect to the southeast corner where Edmond Street and the alley intersect. This area includes the east halves of city blocks 30 and 31, all of city block 40, and the west half of city block 51.

Within the rectangle described by the latitude and longitude coordinates, there is an industrial area. This area is located between the area being nominated and the east bank of the Missouri River. The area is included as a buffer zone to help retard any future encroachments into the historic area from the industrial concerns already located there or by other industries wanting to locate in this area.

In the Market Square Historic District there are nineteen buildings of major importance including Market Square (with seventeen buildings), the Missouri Valley Trust Company, and the Robidoux House, on Edmond Street. These buildings illustrate the use of Renaissance revival architecture for commercial purposes.

MARKET SQUARE

Market Square illustrates the commercial architecture of the 1830's and the 1840's. This design was copied in the buildings of the Midwest from the East as commercial centers expanded out of the frontier towns.

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. #1

MARKET SQUARE HISTORIC DISTRICT

The Square contains seventeen buildings running around one city block with each building joined to the next. These buildings are from two to three floors. Most have flat roofs. The buildings are constructed of brick, stone, cast iron, and wood. The facades of the buildings are divided into bays with no divisionary features between the bays.

Some of the windows are rectangular in shape while others are arched in varying degrees. Most of the windows have some type of over them; some being very elaborate with mouldings shaped like segmental arches, others having only a simple keystone. On the ground floor of several buildings, due to the cast iron supports employed, the window space has been greatly increased allowing for the store front type of window. The easternmost store on the north side of the block has an oriel window on the second floor.

Several of these buildings have very elaborate cornices with large brackets, while others are terminated with a cornice-like structure composed of bricks used in various patterns and designs.

On the whole, the wall surfaces of these buildings are devoid of elaborate ornamentation. Most of the ornamentation is created through the contrast of stone against brick; examples being the stone sills under many of the windows and the string courses found on several facades. Some of the store front windows have "pilasters" which have been fluted for added detail. On several buildings, which have arched windows, the impost line has been emphasized by the application of stone.

One building on the east side of the block, the fourth building from the corner of Felix and Third streets, deserves detailed observation. This building is three storied and has six bays spanning the facade. Each floor is divided from the one below by a lintel and string course. These structures are supported by pilasters which have capitals derived from the Corinthian order. The first floor post and lintel system is the most complete and standard in form. The second and third floor lintels have been formed out of brick and corbeled on the underside. One window is placed between each pair of pilasters on the second and third floors. These windows are elaborately decorated around the upper edge by segmental mouldings and keystones. On the first floor there are store front type windows and the door.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. #2

MARKET SQUARE HISTORIC DISTRICT

MISSOURI VALLEY TRUST COMPANY

Exterior

The Missouri Valley Trust Company is a straight-fronted brick and stone three-story (full basement and two floors) building located on the southeast corner of Fourth and Felix streets. There are two primary facades, one facing north which is eighty feet long and the other facing west which is forty feet long. The other facades are joined on the south and east by other buildings. The north facade is three bays wide, each bay containing paired windows, both floors being identical in window placement. The west facade is only one and a half bays across, each floor having the same basic window placement as the north facade except for the half bay which has single windows on each floor. There is also a single bay which cuts across the corner between the north and west facades. This bay is convex in plan and is projected forward from the main wall. It contains a single window on the second floor and a doorway extending through the basement and first floor levels. Both facades are surmounted by a cornice. There is a flat roof which is typical of many commercial buildings in St. Joseph.

The windows on both facades are tall and arched with keystones, the second floor windows being directly over the first floor windows. Each window has a pivoting sash with one pane of glass. The arch section above is filled with stained glass on the first floor and circular tracery on the second. The section directly above the door in the corner bay is treated in the same manner as the rest of the first floor windows allowing the transition from one facade to the other to be continuous. The only difference with this opening, as opposed to the others, is in the treatment of the details. The same elements have been employed but in a more complex form. The arch has rounded mouldings and to the keystone has been added a bracket-like decoration. The spandrels have also been given more attention with a bas relief of a cornucopia being applied to the wall surface. The first floor windows have recessed decorative brick panels under them. These panels are separated from the window itself by a narrow string course which forms a continuous sill.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. #3

MARKET SQUARE HISTORIC DISTRICT

A cornice-like string course divides the first and second floors on both facades. The second floor windows rest on this string course which provides a continuous sill under them. This string course is not stopped at the edge of each facade that joins the corner bay; it is continued across it and, in the same manner as the window in this section, it is given more detail. This section of the string course has been given more depth, creating an overhang above the doorway.

Several decorative features have been employed on both facades which contrast with the otherwise smooth wall surface. Quoins have been applied to each end of both facades and to the corners of the corner bay on the second floor. These quoins are smooth and beveled at the edges. Rustication matching the quoins has been applied at the division lines of each bay. The rustication takes on the function of pilasters. On the first floor of the corner bay the quoins have been eliminated. In their place pilasters have been applied. These pilasters plus the overhang created by the projecting string course serve to create the illusion of a porch-like entranceway. These doorway pilasters rest on the basement which has been modified at this point to create pedestals for these pilasters.

Above the cornice, centered over the corner bay, a wooden placard has been added. This placard has a tall center section with segmental arch. From it a short balustrade extends south and east crowning the half bays nearest the corner.

Interior

The entrance gives access to a small vestibule area at the basement level with two, short, straight stairways, one oriented east-west and the other oriented north-south, to the first floor level, about four feet above the street level.

The interior space has been arranged to accommodate banking functions. This space is rectangular with partitions along two walls dividing the space into various work areas.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. #4

MARKET SQUARE HISTORIC DISTRICT

A continuous ornate partition, running along the southern side of the room, forms the division between the tellers' cages and the main room. Each teller's cage window is arched and surmounted by an open pediment with urn and swag. The partition section between the floor and the tellers' windows is broken into carved panels with miniature caryatids flanking the panels below each teller's window. Each pair of caryatids is separated from each other by two panels. In front of each teller's window is a brass foot rail.

Running along the east side of the room is another partition which separates the office space from the main room. This section has only one opening which is flanked by caryatids and is topped by an open pediment complete with urn and swag. These caryatids and open pediment are identical to those found on the other partition.

In the southeast corner of the room is a smaller room which juts out into the larger room. A single ornately decorated doorway leads into the room.

The interior is rich in detail. Ornate chandeliers provide the only source of light outside of the light coming through the windows. Columns located behind the south partition are heavily carved in a modified corinthian order. Two beam-like structures located directly over the two partitions are decorated with paneling. On the south side the beam rests on the above mentioned columns. Simple dark moulding runs along the surface of the wall three quarters the way up from the floor. Another moulding runs along the juncture of the ceiling and wall in the office space area. The stained glass transoms above the windows are accentuated by the heavy ornamentation around the window. All the details and features found in the interior are accentuated by a light-colored wall surface.

The floor is tile laid out in geometric patterns. The colors used in the tiles continue the contrasting color scheme used throughout the interior.

A fireplace is located along the north wall between the second and third westernmost windows.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE Missouri	
COUNTY Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. #5

MARKET SQUARE HISTORIC DISTRICT

Alterations

In 1883, the Missouri Valley Trust Company underwent major alterations. The space occupied for business was doubled by taking in the adjoining building, giving them a frontage of forty feet on 4th and seventy-five feet on Felix; at the same time the entire interior was refurnished and refitted in hard wood [sic], and beautifully decorated in fresco and gold; tiled floors and open fireplaces being also added."¹

The basic shape and character of the bank has been retained in spite of the various alterations that have been made. According to an 1887 drawing,² the bank's steps were located on the exterior of the building leading to a door which was located on the same level with the first floor windows. All windows had wooden tracery in the arched section. Wooden mullions, and mouldings running horizontally midway between the base of the window and the arched section, allowed for four panes of glass instead of the present large, single pane. The cornice was supported by large brackets which extended from the upper level of the quoins to the underside of the cornice. These brackets were applied to the surface in pairs, with triple brackets being applied at the junctures of the corner bay and the adjoining facades. Finally, a continuous balustrade topped the building, with a placard placed over the corner bay section of the building.

Sometime between this 1887 drawing and the present, a second entrance was added. The door was inserted into the easternmost window space on the north facade and is located at the same level as the main door in the corner bay.

In the interior, alterations have also been made. According to 1887 and 1894 drawings,³ the east partition has been considerably altered. The partition was not straight in plan, but irregular with one section recessed for several feet near the north facade. In 1887, the upper portion of the east partition was still intact, being a continuation of the southern partition in decorative design. By 1894, however, this upper section had been removed. Since 1894, the partition has again been altered, being made straight and having a central opening. The elements employed are the same as those found on the south partition. These 1887 and 1894 drawings also show the walls and ceiling covered with geometric designs, these now being altered to a light colored surface. Finally, the chandeliers have been replaced, probably due to the change from gas to electricity.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE Missouri	
COUNTY Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. #6

MARKET SQUARE HISTORIC DISTRICT

ROBIDOUX HOUSE

Robidoux House is a two-story building with a mansard roof, constructed of brick, stone, and wood. The building is two bays wide on the second floor and in the mansard section. The first floor is dominated by store front type windows and a deeply recessed doorway. To the west of this section is a second doorway which appears to give access to the second floor.

Six windows span the facade on the second floor, three windows to each bay. These windows are two over two double-hung and are round-arched. Each window is crowned by an elaborate segmental moulding ornamented with a carved keystone and enlarged corner vousoirs. A stone sill is located under each window. There are four dormer windows in the mansard section, two windows to each bay. These windows are similar to the second floor windows in shape and number of panes to each sash. All decorative features have been eliminated and each window is now topped by a miniature pointed gable.

A cornice-like string course divides the first and second floors, while corbeled brickwork, located midway between the upper level of the second floor windows and the cornice, divides the second floor from the mansard section and cornice. These divisionary features divide the facade into three equal horizontal sections.

A cornice is located directly under the dormer windows of the mansard section. The cornice is supported by brackets positioned at the corners of the facade and between the third and fourth windows of the second floor. Between these three brackets are rectangular modillions. A miniature string course runs along the bottom edge of the modillions between the brackets.

Modified quoins have been applied to the western edge of the facade. Rustication, which matches the quoins, is placed at the division between the two bays. These decorative features are confined to the second floor of the building. Besides being decorative, the quoins and rustication act as supports for the corbeled brickwork which spans the facade midway between the second floor windows and the cornice.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

7. #7

MARKET SQUARE HISTORIC DISTRICT

CONDITION

The seventeen Market Square buildings and the Robidoux House are in a deteriorated condition. Little repair has been done. The Missouri Valley Trust Company is, however, in excellent condition. It is one of the few buildings kept in good repair in the historic district.

FOOTNOTES

- ¹Historical and Descriptive Review of St. Joseph, Missouri (New York: John Lethem, 1889), p. 166.
- ²C. H. Dunn & Co., An Illustrated Review of St. Joseph, Missouri (St. Joseph: Lon Hardman, 1887), p. 65.
- ³Ibid., op. p. 65; and The St. Joseph Daily News Souvenir Edition: St. Joseph and Northwest Missouri (St. Joseph: New Printing Co., 1894), p. 69.

3. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

- ☐ Pre-Columbian | ☐ 16th Century | ☐ 18th Century | ☒ 20th Century
☐ 15th Century | ☐ 17th Century | ☒ 19th Century

SPECIFIC DATE(S) (If Applicable and Known)

1850-1940, 1859-60

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

- | | | | |
|--|---|---|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input checked="" type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Philosophy | <input type="checkbox"/> Other (Specify) _____ |
| <input type="checkbox"/> Historic | <input checked="" type="checkbox"/> Industry | <input type="checkbox"/> Science | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Sculpture | _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape Architecture | <input checked="" type="checkbox"/> Social/Humanitarian | _____ |
| <input type="checkbox"/> Art | <input type="checkbox"/> Literature | <input type="checkbox"/> Theater | _____ |
| <input checked="" type="checkbox"/> Commerce | <input type="checkbox"/> Military | <input type="checkbox"/> Transportation | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Music | | |
| <input type="checkbox"/> Conservation | | | |

STATEMENT OF SIGNIFICANCE

The Market Square area of St. Joseph, Missouri encompasses a complete half block of mid-nineteenth century historic buildings at the center of the original town of St. Joseph plus adjacent blocks with related contemporary structures. The area is significant as part of the original plan of the town adopted by the proprietor, Joseph Robidoux IV, on July 26, 1843. Certain donations of land were made for public purposes. Quarter blocks were set aside for a "Public Church," a "Public School," and a "Catholic Church" and the west half of Block 31 was set aside for a public market and was designated "Market Square."¹

Transportation and communication in the early town were largely by river and the situation of Market Square, just two blocks from the river, made it the natural center around which the town developed. The early merchants built ten buildings on the east half of Block 31 next to Market Square. Professional men had their offices on the second floors of the buildings, and, in the early days, residential quarters also existed above the stores and the entire block became known as Market Square.²

In the westward migration the location of St. Joseph was an optimum point in which the relatively comfortable transportation by steamboat was left and the outfitting for the more hazardous trip across the plains by covered wagons was begun. This traffic assumed great proportions after the discovery of gold in California, and it was estimated that in the year 1850, when the permanent population of St. Joseph was recorded as 3,460, some 50,000 emigrants went through St. Joseph--approximately half of the number for the entire country.³

The business of outfitting this great migration, supplying the wagons, the oxen, the provisions, and wares, was the basis for an active, expanding community--all centering about Market Square.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

8. #1

MARKET SQUARE HISTORIC DISTRICT

St. Joseph became known as "The Queen of the River Towns" and in the 1850's there were at times as many as twenty steamboats tied up along the riverfront.⁴ The coming of the railroad in February, 1859, the first cross-state railroad west of the Mississippi and the farthest west in the nation, increased the flow of goods.⁵ The freighting business out of St. Joseph grew to enormous proportions, this being the supply depot for the outlying and advancing civilization. From this enterprise grew a great wholesale business that supplied the entire west.

The movement of population into California during the 1850's brought about a demand for faster mail service than the long passage by sailing ships around Cape Horn, or by mule train across the Isthmus of Panama, or by stagecoach through the southwest or "Ox-bow Route." As a result, the experienced freighting firm of Russell, Majors, and Waddell was called up to operate a "Pony Express" by which relays of riders carried mail from the railhead at St. Joseph across the 2,000 miles to Sacramento, California. This mail service was initiated on April 3, 1860, and ran for eighteen months until the first cross-country telegraph line was completed in October, 1861. During the course of operations the Pony Express riders would pick up mail at the U.S. Express Office. This office was in different locations through the years and at one time was located in Market Square at 108 South Third Street during the time of the Pony Express.

St. Joseph's rapid progress came to a standstill during the Civil War years, but in the 1870's, 1880's, and 1890's the town reached new heights of prosperity.⁶ The great wholesale houses built their new and imposing buildings to the north, east, and south of the old Market Square area where they had made their starts and the center of the business district moved a few blocks eastward.

In this new business district were already located some of the many banks that were in operation in St. Joseph at this time, including the Bank of the State of Missouri at the southeast corner of Felix and Fourth streets, a building now occupied by the Missouri Valley Trust Company.

The Missouri Valley Trust Company building has been continually occupied by banking houses since its erection in 1859. It is believed to be the oldest such building west of the Mississippi.⁷

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

8. #2

MARKET SQUARE HISTORIC DISTRICT

The trust company now occupying the building is also the oldest trust company in St. Joseph, being chartered in March, 1889, with John J. Tootle as president.⁸

The Bank of the State of Missouri in St. Joseph was organized in 1859. Robert W. Donnell, a prosperous wholesale merchant, was the president with A. M. Saxton as cashier. At this time a building located at Felix and Fourth streets was erected at the cost of about \$25,000.⁹ The Pfeiffer Stone Company was commissioned to do the work.

In February, 1866, the bank was re-organized and the firm joined the national banking system under the name of State National Bank. L. M. Lawson was president, A. M. Saxton, cashier, and C. B. France, assistant cashier.

The bank relinquished its national charter in 1871 becoming the State Savings Bank. A. M. Saxton was now president and C. B. France, cashier.

By May, 1881, Saxton had withdrawn from the corporation. C. B. France was elected president, R. L. McDonald was chosen vice-president, and E. Lindsay, cashier. The bank had a capital of \$100,000 and a surplus of \$75,000. The bank retained its state charter until 1890 when it was again made a national bank.

In 1899, the Missouri Valley Trust Company took over the building. The trust company is still in operation today.

These mid-nineteenth century buildings, still standing and in operation, are a monument to the origin of St. Joseph and to the beginnings of many current businesses and professional careers that have been retooled through the years meeting the needs and changing economy of St. Joseph and its extensive trade area.

PRESENT STATUS

The present status of the Market Square Historic District is precarious. It lies within the boundaries of an urban renewal area being considered for central St. Joseph. The plans call for the area between Francis Street and Edmond Street from 6th-8th streets

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

8. #3

MARKET SQUARE HISTORIC DISTRICT

to be the focal point of commercial redevelopment. These four city blocks are to be substantially cleared and converted into a super block with Felix and 7th streets as pedestrian malls.¹⁰ Gradually this block will be extended westward to 4th Street. A proposed motor hotel is to be erected on the Market Square block with a transportation terminal directly to the north in the next block¹¹ (see map #4). The area to the west of 2nd Street is to have substantial clearance.¹² Ramps for the proposed Interstate 229 are to be located at the corner of Market Square at 3rd and Edmond streets. Other ramps are to be at 2nd and Felix streets and 2nd and Francis streets (see map #5).

Past development of the city has already removed the early buildings on the north, south, and west of Market Square, leaving only the seventeen remaining buildings intact.

At present, research is being conducted by the owner concerning the Robidoux House.

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

8. #4

MARKET SQUARE HISTORIC DISTRICT

FOOTNOTES

1. Atlas of the City of St. Joseph (St. Joseph: William H. Floyd & Co., 1884), p. 5.
2. St. Joseph City Directories (N. Pl.: N. Pub., 1868-1905).
3. Charles van Ravenswaay, ed., Missouri: A Guide to the "Show Me" State (New York: Duell, Sloan, and Pearce, 1941), p. 286.
4. Chris L. Rutt, History of Buchanan County and the City of St. Joseph, 1826-1904 (Chicago: Biographical Publishing Co., 1904), p. 256.
5. Lucinda Templin, "The Development of Railroads in Missouri to 1860" (unpublished Master's Thesis, University of Missouri, Columbia, 1915), p. 126; and van Ravenswaay, 1941, p. 286.
6. Historical Atlas Map of Buchanan County, Missouri (Philadelphia: Brink, McDonough & Co., 1877), p. 14; and Annual Report of Board of Trade (St. Joseph: N. Pub., 1886), p. 37.
7. Dorothy J. Caldwell, ed., Missouri Historic Sites Catalogue (Columbia: State Historical Society of Missouri, 1963), p. 15.
8. Roy Coy, ed., Museum Graphic (St. Joseph: St. Joseph Museum, Winter, 1959), p. 5.
9. History of Buchanan County, Missouri (St. Joseph: Union Historical Co., 1881), p. 621.
10. St. Joseph, Missouri, General Neighborhood Renewal Plan [Missouri R-65 (GN)] (N. Pl.: N. Pub., June 1, 1969), p. 6.
11. Ibid., p. 27.
12. Ibid., p. 28.

9. MAJOR BIBLIOGRAPHICAL REFERENCES

SOURCES CITED

1. Annual Report of Board of Trade. St. Joseph: N. Pub., 1886.
2. Atlas of the City of St. Joseph. St. Joseph: William H. Floyd & Co., 1884.
3. Caldwell, Dorothy J. (ed.). Missouri Historic Sites Catalogue. Columbia: State Historical Society of Missouri, 1963, p. 15.

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			OR	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	Degrees Minutes Seconds
NW	39 ° 46 ' 27 "	94 ° 51 ' 12 "		0		
NE	39 ° 46 ' 27 "	94 ° 51 ' 02 "				
SE	39 ° 46 ' 18 "	94 ° 51 ' 02 "				
SW	39 ° 46 ' 18 "	94 ° 51 ' 12 "				

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: 7.8 acres

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

11. FORM PREPARED BY

NAME AND TITLE:

M. Patricia Holmes, Chief Architectural Historian

ORGANIZATION

Missouri State Park Board

DATE

State Historical Survey and Planning OfficeJanuary 12, 1972

STREET AND NUMBER:

P.O. Box 176, 1204 Jefferson Building

CITY OR TOWN:

Jefferson City

STATE

Missouri 65101

CODE

29

12. STATE LIAISON OFFICER CERTIFICATION

NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National ☐ State ☒ Local ☐

Name

Joseph Jaeger, Jr.

Title Director, Missouri State Park Board, and Missouri State Liaison Officer for P.L. 89-665

Date

I hereby certify that this property is included in the National Register.

Chief, Office of Archeology and Historic Preservation

Date

ATTEST:

Keeper of The National Register

Date

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES
INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE	
Missouri	
COUNTY	
Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

9. #1 MARKET SQUARE HISTORIC DISTRICT
4. Coy, Roy (ed.). Museum Graphic. St. Joseph: St. Joseph Museum, Spring, 1949-Winter, 1970.
5. Dunn, C. H. & Co. An Illustrated Review of St. Joseph, Missouri. St. Joseph: Lon Hardman, 1887, pp. op. 8, 58, op. 65, 65.
6. Historical and Descriptive Review of St. Joseph, Missouri. New York: John Lethem, 1889, p. 166.
7. Historical Atlas Map of Buchanan County, Missouri. Philadelphia: Brink, McDonough & Co., 1877.
8. History of Buchanan County, Missouri. St. Joseph: Union Historical Co., 1881.
9. Rutt, Chris L. History of Buchanan County and the City of St. Joseph, 1826-1904. Chicago: Biographical Publishing Co., 1904.
10. St. Joseph City Directories. N. Pl.: N. Pub., 1868-1905.
11. St. Joseph Daily News Souvenir Edition: St. Joseph and Northwest Missouri. St. Joseph: New Printing Co., 1894, p. 69.
12. St. Joseph, Missouri, General Neighborhood Renewal Plan [Missouri R-65 (GN)], a report prepared for the Land Clearance for Redevelopment Authority of St. Joseph, Missouri, by Howard, Needles, Tammen, and Bergendoff, consulting engineers, Kansas City, Missouri, June 1, 1969. Filed at the Missouri State Park Board's central office, P. O. Box 176, 1204 Jefferson Building, Jefferson City, Missouri 65101.
13. Templin, Lucinda. "The Development of Railroads in Missouri to 1860." Unpublished Master's Thesis, University of Missouri, Columbia, 1915.
14. van Ravenswaay, Charles (ed.). Missouri: A Guide to the "Show Me" State. New York: Duell, Sloan, and Pearce, 1941.

NATIONAL REGISTER OF HISTORIC PLACES
 INVENTORY - NOMINATION FORM

(Continuation Sheet)

STATE Missouri	
COUNTY Buchanan	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)


9. #2 MARKET SQUARE HISTORIC DISTRICT

OTHER PERTINENT SOURCES

1. Campbell, R. A. Campbell's Gazetteer of Missouri. St. Louis: R. A. Campbell, Publisher, 1874, p. 82b.
2. History of Buchanan County and St. Joseph, Missouri. St. Joseph: St. Joseph Publishing Co., 1898, pp. 306, 516.
3. History of Buchanan County and St. Joseph and Representative Citizens. Chicago: Biographical Publishing Co., 1904, pp. 188-189, 357-58.
4. History of Buchanan County and St. Joseph, Missouri. St. Joseph: Midland Printing Co., 1915.
5. Howard, Robert W. Hoofbeats of Destiny. New York: The New American Library, 1960.
6. Illustrated St. Joseph Today. N. Pl.: N. Pub., 1903-04, p. 21.
7. Lawrence, Philip A., Jr., A.I.A. Architectural Report, received Summer, 1971, filed at Missouri State Park Board's central office, P.O. Box 176, 1204 Jefferson Building, Jefferson City, Missouri 65101.
8. New York Times, January 5, 1892, p. 5.
9. Portrait and Biographical Record of Buchanan and Clinton Counties, Missouri. Chicago: Chapman Bros., 1893, pp. 151-52.
10. St. Joseph, Missouri Today (1927). St. Joseph: Chamber of Commerce, 1927.
11. Settle, Mary L. and Raymond W. War Drums and Wagon Wheels: The Story of Russell, Majors, and Waddell. Lincoln: University of Nebraska Press, 1966.
12. Shoemaker, Floyd Calvin, L.L.D. Missouri and Missourians. Chicago: Lewis Publishing Co., 1943, pp. 409, 442.
13. Utz, Nellie. "History of the Growth and Development of St. Joseph, 1857-1858." Unpublished Master's Thesis, University of Kansas, Lawrence, 1935.
14. Williams, Walter. A History of Northwest Missouri. 3 vols. Chicago: Lewis Publishing Co., 1915.

APPROXIMATE MEAN
DETERMINATION, 1924

TRUE NORTH
MAGNETIC NORTH



CONTOUR INTERVAL 20 FEET
DATUM IS MEAN SEA LEVEL

NEW MARKET 17 MI.
KANSAS CITY (CIVIC CENTER) 54 MI.

GOWER 15 MI.
KANSAS CITY (CIVIC CENTER) 53 MI.

Polconic projection. 1927 North American datum
10,000-foot grid based on Missouri (West)
rectangular coordinate system
1000-meter Universal Transverse Mercator grid ticks,
zone 15, shown in blue

Lat	Long
NW 39° 46' 27"	94° 51' 12"
NE 39° 46' 27"	94° 51' 02"
SE 39° 46' 18"	94° 51' 02"
SW 39° 46' 18"	94° 51' 12"

U.S.G.S. 15' Quadrangle
"St. Joseph" (1924)
Scale 1:62500
Market Square Historic District


ST. JOSEPH, MO.-KANS.


N3945-W9445/15


1924

MAP 1

MAP 2







LEGEND

FIRST PROJECT AREA ———
G.N.P. BOUNDARY - - - - -


MAP 5

SCALE - 1" : 400'

FELIX ST.

MARKET PLACE

31



N. 3rd St.


EDMOND ST.

N


MARKET SQUARE HISTORIC DISTRICT —
MARKET SQUARE
ST. JOSEPH, MISSOURI

MAP 6
M.S.H.S.

FELIX ST.



MARKET SQUARE



N 3rd St.

EDMOND ST.



Chamber of
Commerce Building

MARKET SQUARE HISTORIC DISTRICT

M.S.H.S.

March 2, 1971
S. Teczar

MARKET SQUARE HISTORIC DISTRICT

COUNTY:	Buchanan
LOCATION:	St. Joseph, Mo.
OWNER:	Multiple private ownership (See Site File Copy)
ADDRESS:	See Site File Copy
DATE APPROVED BY A.C.:	05-15-71
DATE SENT TO JEFF. CITY:	02-17-72
DATE SENT TO D.C.:	02-22-72
DATE OF REC. IN D.C.:	02-28-72
DATE PLACED ON NATIONAL REGISTER:	03-17-72
DATE AWARDED CERTIFICATE (AND PRESENTOR):	04-30-73 (represented 05-06-73) John Harr - AC member
DATE FILE REVIEWED:	

MARKET SQUARE HISTORIC DISTRICT

#147

COUNTY:	Buchanan
LOCATION:	St. Joseph
OWNER:	Multiple Private
ADDRESS:	See Item 4 of nomination
DATE APPROVED BY A.C.:	May 15, 1971
DATE SENT TO D.C.:	February, 1972
DATE OF REC. IN D.C.:	February, 1972
DATE PLACED ON NATIONAL REGISTER:	March 17, 1972
DATE CERTIFICATE AWARDED (AND PRESENTOR):	
DATE FILE REVIEWED:	

Form 10-301
(July 1969)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES
PROPERTY MAP FORM

(Type all entries - attach to or enclose with map)

STATE	Missouri
COUNTY	Buchanan
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

1. NAME
COMMON:
AND/OR HISTORIC:

2. LOCATION
STREET AND NUMBER:

CITY OR TOWN:

STATE:

CODE	COUNTY:	CODE
29	Buchanan	021

3. MAP REFERENCE
SOURCE:
SCALE:
DATE:

4. REQUIREMENTS

- TO BE INCLUDED ON ALL MAPS
1. Property boundaries where required.
 2. North arrow.
 3. Latitude and longitude reference.

Map #3

SEE INSTRUCTIONS

MARKET SQUARE HISTORIC DISTRICT ST. JOSEPH, MISSOURI BUCHANAN COUNTY

enclosed
parking lot
more recent

vacant lot

construction

INDUSTRIAL

AREA

2ND STREET

extant bldgs.
more recent
construction
than district,
not compatible
with district

MARKET SQUARE

3RD STREET

extant building
more recent
construction
than district

30

extant buildings
more recent construction
than district

41

extant bldgs.
mixture of
construction
periods, some
bldgs. compat-
ible with
district

50

bank with
drive-in
facilities

parking lot

40

4TH STREET

FELIX STREET

MISSOURI VALLEY
TRUST CO.

extant bldgs.
more recent
construction
than district

51

EDMOND STREET

extant buildings
more recent construction
than district

extant buildings
more recent
construction than
district



AREA OF MAJOR IMPORTANCE



AREA OF IMPORTANCE



AREA OF NO IMPORTANCE OR UNDETERMINED VALUE



MARKET SQUARE HISTORIC DISTRICT

DI. NOTES AREA NOMINATED TO THE NATIONAL REGISTER

SCALE: 1"=10'

M.S.H.S.

NOVEMBER 26, 1971.

S. TECZAR

MARKET SQUARE HISTORIC DISTRICT ST. JOSEPH, MISSOURI BUCHANAN COUNTY

enclosed
parking lot
more recent

construction

extant building
more recent
construction
than district

30

INDUSTRIAL

10

20

AREA

11

20

2ND STREET

extant bldgs.
more recent
construction
than district,
not compatible
with district

MARKET PLACE

MARKET
SQUARE

3RD STREET

Industrial Area

vacant lot

vacant lot



AREA OF MAJOR IMPORTANCE



AREA OF IMPORTANCE



AREA OF NO IMPORTANCE OR UNDETERMINED VALUE

MARKET SQUARE HISTORIC DISTRICT

DI. NOTES AREA NOMINATED TO THE NATIONAL REGISTER

SCALE: 1"=10'

FRANCIS STREET

extant buildings
more recent construction
than district

40

FELIX STREET

bank with
drive-in
facilities

40

parking lot

4TH STREET

extant bldgs.
mixture of
construction
periods, some
bldgs. compat-
ible with
district

50

MISSOURI VALLEY
TRUST CO.

extant bldgs.
more recent
construction
than district

50

EDMOND STREET

extant buildings
more recent construction
than district

extant buildings
more recent
construction than
district

M.S.H.S.

NOVEMBER 26, 1971.

STECZAR

MARKET SQUARE HISTORIC DISTRICT
ST. JOSEPH, MISSOURI
BUCHANAN COUNTY

enclosed
parking lot
more recent

construction

vacant lot

FRANCIS STREET

extant buildings
more recent construction
than district

extant buildings
more recent
construction
than district

extant bldgs.
mixture of
construction
periods, some
bldgs. compat-
ible with
district

extant bldgs.
more recent
construction
than district,
not compatible
with district

bank with
drive-in
facilities

51 extant bldgs.
more recent
constructi
than distr

Industrial area

vacant lot

vacant lot

EDMOND STREET

extant buildings
more recent construction
than distributed

extant buildings
more recent
construction than
district

AREA OF NO IMPORTANCE OR UNDETERMINED VALUE

AREA OF IMPORTANCE

AREA OF NO IMPORTANCE OR UNDETERMINED VALUE

MARKET SQUARE HISTORIC DISTRICT

DI NOTES AREA NOMINATED TO THE NATIONAL REGISTER

SHSM

NOVEMBER 26, 1971.

STECZAR

SCALE: 1=100

MAP 3

Name of Site: Market Square Historic District
Site Number _____
Photographer: _____
Date of Photo: _____
View of Photo: Market Square - plan from city maps 1897-1911
Neg. Size _____

MISSOURI-STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

FELIX ST.

SO. SECOND ST.

MARKET SQUARE

SO. THIRD ST.

EDMOND ST.

CITY HALL
MARKET ON 1ST FLOOR
CITY OFFICES ON 2ND FLOOR

PLAT OF ORIGINAL TOWN - ST. JOSEPH MO.
MARKET SQUARE AREA

REFERENCE: CITY MAPS OF 1897 - 1901
DRAWN MARCH 1971 - LEBELUS - SCALE: 1" = 20'

KEY

- 1" = 20'
- HEIGHT
- STONE
- FRAME
- DRINK
- AT 50'
- HEIGHT
- ABOVE
- ELEVATION
- SKYLIGHT
- WINDO
- FIRE
- BAREN

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District

Site Number

Photographer:

Date of Photo:

View of Photo: Market Square - plan from city maps 1897-1911

Neg. Size


FELIX ST.

SP. SECOND ST.

MARKET SQUARE

SP. THIRD ST.

EDMOND ST.



PLAT OF ORIGINAL TOWN - ST. JOSEPH MO.
MARKET SQUARE AREA

REFERENCE CITY MAPS OF 1897-1901
DRAWN MARCH 1911 - L. B. LILLIS - SCALE = 1" = 20'

KEY

- HEIGHT OF STORY OR FRAME FOR DRIVEWAY AT EACH CORNER
- HEIGHT OF ABOVE RAILROAD ELEVATION
- WINDOWS
- FIRE ESCAPE
- BASEMENT

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Technical Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District

Site Number

Photographer:

Date of Photo:

View of Photo: Market Square - plan from city maps 189

Neg. Size

55
SECOND ST.

MARKET SQUARE

SO. THIRD ST.

EDMOND ST.

PLAT OF ORIGINAL TOWN - ST JOSEPH MO.
MARKET SQUARE AREA

REFERENCE - CITY MAPS OF 1897 - 1911
DRAWN MARCH 1971 - L. BELLIS - SCALE = 20

KEY

HEIGHT	WEIGHT
STOMACH	STOMACH
DRINK	DRINK
AT 5	AT 5
HEALTH	HEALTH
ABUSE	ABUSE
ELDER	ELDER
SMALL	SMALL
WIND	WIND
SHIRT	SHIRT
BASE	BASE

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia National Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District

Site Number

Photographer:

Date of Photo:

View of Photo: Market Square - plan from city maps 1897-1

Neg. Size

501 SECOND ST.


MARKET SQUARE

50. THIRD ST.

EDMOND ST.

PLAT OF ORIGINAL TOWN - ST JOSEPH MO.
MARKET SQUARE AREA

REFERENCE - CITY MAPS OF 1897 - 1911
DRAWN MARCH 1971 - L.B.L. - SCALE = 20



Historic District
Name of Site: Market Square - Buchanan Co.

Site Number: _____

Photographer: Don Reynolds

Date of Photo: Dec. 1970

View of Photo: Market Square - corner of Edmund and
corner building

Neg. Size: _____

3rd streets, looking northwest

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Name of Site: _____
Site Number: _____
Photographer: _____
Date of Photo: _____
View of Photo: _____
Neg. Size: _____

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



10-8-71

facing east - Block 34, West side

Name of Site: Market Square Historic District

Site Number _____

Photographer: Don Reynolds

Date of Photo: August, 1971

View of Photo: Market Square Historic District - buildings along 4th Street

between Felix and Edmund Streets
Looking east

ST. JOSEPH MUSEUM
ST. JOSEPH, MO.

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Markoe Square Historic District
Site Number: Missouri State Park Board
Photographer: Jan., 1972
Date of Photo: copy photo: interior view of the
View of Photo: Mo. Valley Trust Co.
Neg. Size: 35 mm
in 1894 when the
park was operating
under the name
of State National
Bank. From the
St. Joseph Daily News
Souvenir Edition:
St. Joseph and
Northwest Mo., 1894,
p. 69.



MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District

Site Number

Photographer: Missouri State Park Board


Date of Photo: Jan., 1972

View of Photo: Copy photo:

Neg. Size

35 mm

interior view of the Missouri Valley
Trust Co. in 1887 when the bank
was operating under the name of
State Savings Bank. From C. H.
Dunn & Co., An Illustrated Review of
St. Joseph, Mo., 1887, op. p. 65.



Name of Site: Market Square Historic District
Site Number _____
Photographer: Don Reynolds
Date of Photo: November 1970
View of Photo: Market Square
Neg. Size _____

northwest corner showing all of the
north side and the north end of the
west side, view from northwest
looking southeast.

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Historic District
Name of Site: Market Square - Buchanan Co.

Site Number

Photographer: Don Reynolds

Date of Photo: Nov. 1950

View of Photo: Market Square - view of west side of 3rd Street between Francis and Felix streets looking northwestward

Neg. Size

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Name of Site: Market Square - Buchanan Co.

Site Number

Photographer: Don Reynolds

Date of Photo: Nov. 1970

View of Photo: Market Square - 3rd building from the corner of Felix and 3rd street
looking west across 3rd street


Neg. Size

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Historic District
Name of Site: Market Square - Buchanan Co.
Site Number _____
Photographer: Don Reynolds
Date of Photo: Nov. 1970
View of Photo: Market Square - 3rd Street looking west,
2 buildings at the corner of 3rd and
July streets
Neg. Size _____

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Don R.
8-71

Don Reynolds
Sept 71

Name of Site: Market Square Historic District
Site Number
Photographer: Don Reynolds
Date of Photo: September, 1971
View of Photo: Missouri Valley
Neg. Size
Trust Company - interior view,
view looking southeastward

ST. JOSEPH MUSEUM
ST. JOSEPH, MO.

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Name of Site: Market Square Historic District

Site Number _____

Photographer: Don Reynolds

Date of Photo: November, 1970

View of Photo: Market Square - east side - view from southeast
looking northwest

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Name of Site: Market Square Historic District

Site Number

Photographer: Dor Reynolds

Date of Photo: November, 1970

View of Photo: Market Square - North end

Neg. Size

North end
northwest

on west side, view from
looking south east.

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Name of Site: Market Square Historic District

Site Number _____

Photographer: Don Reynolds

Date of Photo: November, 1970

View of Photo: Market Square -

Neg. Size _____


East side of block, view from southeast
looking northwest.

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District
Site Number: _____
Photographer: Missouri State Park Board
Date of Photo: June, 1972
View of Photo: Copy photo: exterior view of Mo. Valley
Neg. Size: 35 mm Trust Co. in 1887 when
the bank was operating
under the name of
State Savings Bank.
from C. H. Dunn & Co.,
An Illustrated Review
of St. Joseph, Mo, 1887,
p. 65.



Name of Site: Market Square Historic District

Site Number

Photographer: Don Reynolds

Date of Photo: November 1970

View of Photo: Market Square

Neg. Size

— mid section of west side, view
from southwest looking northwest

MISSOURI STATE PARK
State Historical Survey and
Suite 215, Columbia Profes
909 University Av
Columbia, Missouri



Historic District
Name of Site: Market Square - Buchanan Co.

Site Number

Photographer: Don Reynolds

Date of Photo: Nov. 1970

View of Photo: Market Square

Neg. Size

- Felix Street, looking south
building on the corner of Felix and 3rd streets
detail, oval window on second floor

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



E.H. MEYER MKT.
WHOLESALE & RETAIL

Name of Site: Market Square Historic District

Site Number _____

Photographer: Don Reynolds

Date of Photo: _____

View of Photo: Market Square

Neg. Size _____

Historic District - Block north of Market Square
view of west side of 3rd Street between F
and Felix streets looking northwest

ST. JOSEPH MUSEUM
ST. JOSEPH, MO.

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Name of Site: Market Square Historic District
 Site Number
 Photographer: Don Rupprecht
 Date of Photo: August, 1971
 View of Photo: Market Square Historic District - building at
Neg. Size northeast corner of 4th & Edmund streets

ST. JOSEPH MUSEUM
ST. JOSEPH, MO.

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District

Site Number

Photographer: Missouri State Park Board

Date of Photo: Jan. 1972

View of Photo:

Neg. Size

copy photo: interior view of the Missouri Valley
Trust Co. in 1887 when the bank
was operating under the name of
State Savings Bank. From C. H.
Dunn & Co, An Illustrated Review of
Joseph, Mo., 1887, op. p. 65.



MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District

Site Number

Missouri State Park Board

Photographer:

January, 1972

Date of Photo:

interior view of the
Mo. Valley Trust Co.

View of Photo:

Neg. Size

35 mm

in 1894 when the
bank was operating
under the name of
State National Bank.
From the St. Joseph
Daily News Examiner
Edition: St. Joseph
and Northwest Missouri

1894, p. 69.



Mo. Valley Trust Bunkle
Don Reynolds Sept 21

Inter. Bldg.

Name of Site: Market Square Historic District

Site Number _____

Photographer: Don Reynolds

Date of Photo: September, 1971

View of Photo: Missouri Valley Trust Company - interior view,
detail of window showing
stained glass transoms


Neg. Size _____

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District
Site Number
Photographer: Missouri State Park Board
Date of Photo: Jan., 1972
View of Photo: interior view of the
Neg. Size: Mo. Valley Trust Co.
35 mm
in 1894 when the
bank was operating
under the name of
State National
Bank. from the
St. Joseph Daily News
Lantern Edition:
St. Joseph and
Northwest Mo., 1894,
p. 69.



MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201

Name of Site: Market Square Historic District


Site Number

Photographer: Missouri State Park Board

Date of Photo: June, 1972

View of Photo: copy photo: interior view of the Mo. Val

Neg. Size 35 mm in 1887 when the bank was
operating under the name
State Savings Bank. From
Deann & Co., An Illustration
of St. Joseph, Missouri, 18



Rel. Wm D.C.

Not Necessary

30d12

Name of Site:

Marble Square Historic District

Site Number

Don Reynolds

Photographer:

Sept. 1971

Date of Photo:

View of Photo:

Reg. Size

West Co. - interior view
showing partitions,
columns, chandeliers
and decorative features
view looking southward



Dak
11-70

Name of Site: Market Square Historic District
Site Number: _____
Photographer: Rox Reynolds
Date of Photo: November, 1970
View of Photo: Market Square - southeast building of the block,
view from southeast
Neg. Size: _____

ST. JOSEPH MUSEUM
ST. JOSEPH, MO.

MISSOURI STATE PARK BOARD
State Historical Survey and Planning Office
Suite 215, Columbia Professional Building
909 University Avenue
Columbia, Missouri 65201



Name of Site: Market Square Historic District

Site Number

Photographer:

Date of Photo: 7 Sept, 1971

View of Photo: Don Reynolds

Neg. Size

Mo. Valley Trust Co. - interior view,
detail of typical, first floor
windows showing stained
glass transoms.

